





PUBLIC INFORMATION MEETING

No. Hero – Grand Isle Bridge

January 12, 2016





Presentation Summary



Project Status

Selected Alternative

Construction Manager/ General Contractor Project Delivery

Discussion



01 PROJECT BACKGROUND/CONSTRAINTS

- Current Bridge Constructed in 1953
 - Twin Leaf Bascule design
 - Two 11'-0" travel lanes with 4'-0" ft. shoulders
 - 80 ft. navigation channel and unlimited vertical clearance
 - Operational reliability
- Project Constraints
 - o Roadway detour is significant
 - Historic Structure
 - Environmental Impacts for alignment change
 - Bridge Condition



01 OUTREACH ACTIVITIES,

Project Website:

http://nhgi.vtransprojects.vermont.gov/

Surveys mailed
Public Information Meeting 07/2014
Web Site Updates





CONTACT

Public Outreach Manager

Mary O'leary of EIV Technical Services (EIV) is serving as the team's public outreach manager. She is supported by a public outreach coordinator, Jacqueline Dagesse, who is also from EIV. Together they will be working with the local towns, community members, businesses, and other stakeholders to provide clear and concise information to enable the public to make informed decisions about the project.

During the public comment period, contact information will be posted. Should a question or issue arise prior to a project meeting or the public comment period, you may contact Jacqueline Dagesse at (802) 497-3653 or idagesse@eivtech.com.

Submit Your Comments

First Name	
Last Name (required)	
Address	
Apt./Suite No.	
Town	

01 PROJECT SCHEDULE

Project Kick off 3/2014

Local Concerns Meeting 5/2014

Scoping Report Development 4/2015

Alternative Selection 6/2015

Concept Design 9/2015

CMGC Selection 10/2015



Design Development 12/2015 thru 9/2016

Interim Repairs 1/2016 thru 5/2016

Construction Contract Award (estimated) 12/2016

Construction(estimated) 5/2017 thru 12/2019

Project Substantial Completion (estimated) 10/2019



02 SELECTED ALTERNATIVE


Twin Leaf bascule
Two travel lanes
11ft. Lane width
5 ft. clearance
Maintain the Historic Look



02 CONSTRUCTION STAGING PLAN



Stage 1 remove one lane Single lane traffic




Stage 2 New span Single lane on new leaf



Stage 3 remove lane 2 Remove old leaves

02 FINAL STAGE

- Install new span
- Tie leaves together
- Two way traffic
- Final commissioning



02 CONSTRAINT MITIGATION

- Roadway Detour route approximately 50 miles
 - Mitigation is Staged Construction Single lane open at all times
- The bridge has context in the community (only highway movable bridge in VT)
 - Mitigation is twin leaf bridge with similar visual impact
- Is the only navigation route for travel from East to West with unobstructed access
 - o Mitigation is install a temporary operating system during construction
 - Scheduled navigation outages with advance notice to mariners






03 CMGC PROCESS DESCRIPTION

Construction Manager/General Contractor

Two Phases

- Design Phase
 - Identify and Mitigate Risk
 - Final Design
 - GMP for Construction
- Construction



03 N HERO CMGC ACTIVITIES

Design Development 60%, 100%

Development of Guaranteed Maximum Price

Award or New Bid Prices

Field Construction

Commence construction

Outages – single lane operation

Substantial completion

Turn over to VTrans



